**GOVERNMENT OF ANDHRA PRADESH**
**ABSTRACT**

Municipal Administration & Urban Development Department – Integrated Andhra Pradesh State Secretariat and Head of Departments (GAD & HOD Towers) office buildings at Amaravati Government Complex, Amaravati - Rates for certain Non-SoR items – Approved – Orders – Issued.

==========

**MUNICIPAL ADMINISTRATION & URBAN DEVELOPMENT (CRDA) DEPARTMENT**

**G.O.Rt.No.275** **Dated: 07-04-2025**

**Read the following:-**

1. G.O.Ms.No.134, MA & UD (CRDA) Dept., Dt.20.12.2014.
2. Lr.No.ENC/IW/SE(P&M)/EE.I/DEE.2/AEE.3/5$^{th}$BoCEs-2025 APCRDA/ 2066, Dt.27.03.2025 of the Engineer – In – Chief (AW/IW)(FAC) & Chairman, BoCEs, Irrigation Compound, Vijayawada.
3. From the Commissioner, CRDA, Vijayawada, Lr.No.MAU61-USI0HB (ITWR)/6/2025-HB, Dt.01.04.2025.

***

**ORDER:**

In the circumstance as reported by the Commissioner, Andhra Pradesh Capital Region Development Authority, Vijayawada in the reference 3$^{rd}$ read above and after careful consideration, Government hereby approve the following Non-SoR item rates as recommended by the Board of Chief Engineers (BoCEs) in the reference 2$^{nd}$ read above, as the rates are work specific and for finished item of work.

| S. No | Description of item | Unit | Approved Rate in Rs. |
|---|---|---|---|
| 1 | STRUCTURAL STEEL FLOOR BEAMS - Supply, transportation, delivery to workshop site, preparation of shop drawings, fabrication with specialized ornamental designs as per drawings, with SAW/MAW/MIG welding process, Assembling, Hoisting and Erecting in position, detailing of I Section floor beams, Base plates for composite structure including making connecting plates of thickness specified in relevant drawings & conforming to IS 2062 with Grade YST 350, in profile as per approved drawings, including cutting, threading, machining, all leads and lifts up to all heights, tools and plants and necessary platforms and scaffolding etc. required for all operations. including the cost for application of primer and 2 hour fire rated Vermiculite paint. | MT | 2,45,335/- |
| 2 | STRUCTURAL STEEL DIAGRIDS - Supply, transportation, delivery to workshop site, preparation of shop drawings, fabrication with specialized ornamental designs as per drawings, with CNC cutting and drilling holes, SAW/MAW/MIG welding process, dry assembling on approved Jigs and transportation work site to AP Amaravati with protection using wooden packaging | MT | 2,87,200/- |

| | | | |
|---|---|---|---|
| | Assembling, Hoisting and Erecting in position including cost of YST 350 grade steel confirming to IS 2062, cost of Gusset plates for Floor beam & Diagrid junctions, diagrid connections as specified in relevant drawings and cutting, threading, machining, all leads and lifts up to all heights, tools and plants and necessary platforms and scaffolding etc. required for all operations with 2 coats of Intergard 251 of 75 micron Primer for receiving Intumescent Paint Upto 50 Floors as shown in the drawing. | | |
| 3 | Cost for Jump-in/Hydraulic / Automatic Wall Form work. Shuttering material cost (One Time) for Jump-in / Hydraulic Automatic. | Sqm | 2610/- |

2. The approved rates mentioned above shall apply only to the above specific work. The Engineer-in-Chief & Group Director, APCRDA is requested to instruct field staff to prepare the observed data based on the details noted during execution of the above structure for future requirements.

3. The Commissioner, AP CRDA, Vijayawada shall take further necessary action, accordingly.

**(BY ORDER AND IN THE NAME OF THE GOVERNOR OF ANDHRA PRADESH)**

**S SURESH KUMAR**
**PRINCIPAL SECRETARY TO GOVERNMENT**

To
The Commissioner, Andhra Pradesh Capital Region Development Authority, Vijayawada.

**Copy to:-**

The Water Resource (Irrigation) Dept., AP Secretariat, Velagapudi.
The Engineer-in-Chief (AW/IW) & Chairman, BoCEs, Water Resources Department, Vijayawada.
The PS to Hon'ble Minister for MA&UD
The PS to Principal Secretary to Government, MA&UD Dept.,
Sf/Sc.

**//FORWARDED : : BY ORDER//**

**SECTION OFFICER**